



Construction Management And Inspection



Auburn Boulevard – Water Main Replacement Project

Project Data

Owner:
Citrus Heights Water District

Project Type:
New Distribution Pipeline

Project Duration:
Sept. 2011 – March 2012

Construction Value:
\$1.29 Million

CM / Inspection:
ICM Group, Inc.

Designer:
Mark Thomas

Contractor:
Mountain Cascade, Inc.

PROJECT OVERVIEW

The Auburn Boulevard Water Main Replacement Project consisted of the installation of over 3,000 lineal feet of 12 inch water main, and approximately 1,000 lineal feet of 8 inch and 6 inch water main. 45 main valves, 9 fire hydrants, and 23 water services were also installed. Plus, 12 tie-in connections to the existing distribution system. This project was located in a heavy traffic zone between I-80 and Antelope Rd.

SERVICES PROVIDED

ICM Group, Inc. provided inspection services and assisted the district's project manager in processing submittals, RFI's, progress payments and communication and coordination with outside agencies. Our services included inspection of construction materials and methods, pipeline disinfection, pressure testing and coordination of mainline shut downs for inter connections to their existing water system.