



## Olive Ranch– Water Main Project

### Project Data

**Owner:**  
San Juan Water District

**Project Type:**  
New Pipeline

**Project Duration:**  
2013

**Construction Value:**  
\$250,000

**Inspection:**  
**ICM Group, Inc.**

**Contractor:**  
Teichert Construction

### PROJECT OVERVIEW

New 6" C900 water main and 1" poly water services were installed for this 15 home subdivision. Appurtenances included mainline gate valves, hydrant laterals, blow offs and air relief valves. Also, a hot tap was completed at the existing water main using a stainless steel tapping sleeve to provide water to the subdivision.

### SERVICES PROVIDED

ICM Group, Inc. provided inspection services and document control for the duration of the project. Services included inspection of construction materials and methods, coordination with SJWD's project manager and operations staff and oversight for commissioning of the new water system. Activities included flushing, chlorination/disinfection and pressure testing, following written specifications and AWWA standards.