



Ceres River Bluff Reservoir and Pump Station Project

Project Data

Owner:
City of Ceres

Project Types:
Pump Station
Tank
Pipeline

Project Duration:
2021 - 2022

Construction Value:
\$15 Million

CM / Inspection:
ICM Group, Inc.

Designer:
Blackwater Consulting

Contractor:
Garney Construction

PROJECT OVERVIEW

The Project consisted of the construction of local facilities to serve as the SRWA finished water terminal system and be integrated into the Ceres water distribution system. Components included 3 million gallon DN tanks, 10 mgd booster pump station, electrical building, 500ft of 18" to 30" onsite piping, about 4,000ft of 18" potable water main, I&Cs, valves, blow offs, and other ancillary equipment, and site civil improvements.

SERVICES PROVIDED

ICM Group provided Construction Management and Inspection for this project. Services included the inspection and testing of construction materials and methods, processing RFIs, submittals, and progress payments. ICM Group coordinated with the City for change order review and execution, claims mitigation, and Final Payment.